

1 040868

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham-Michaelis Corporation

Name & Address P.O. Box 247

Wichita, KS 67201

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 13 Month: 7 Year: 19 94

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

vers: $5\frac{1}{2}$ " at 5199' w/125 sx cement, Perfs at 5126-30, 5132-36, 5100-06'

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug at 1005' with 50 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)Plugging Operations attended by Agent: All Part None

Operations Completed: Hour: 3 p.m. Day: 13 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped down $5\frac{1}{2}$ " casing with 200 lbs. hulls and 25 sx cement. Stopped plug at 4900',2nd plug loaded hole with drilling mud and spotted plugs through $5\frac{1}{2}$ " casing: pumped 50 sx cement at 1050',

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3230' of $5\frac{1}{2}$ " casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

XXXXXX observe this plugging.

DATE 7-21-94

INV. NO. 40841

7-13

7-13

API NUMBER 15- 097-20,094-0000
 4 SE SW, SEC. 4, T 30 S, R 19 W/X
 660 feet from S section line
 3300 feet from E section line

Lease Name Dean Well # 1-4

County Kiowa

Well Total Depth 5205 169, 16 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1004

Signed 
(TECHNICIAN)FORM C
Rev. 1