

1 050999

1-28-8815-097-20175-00088

API NUMBER 15- Drill Completion Date 9/13/73

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE SE, SEC. 4, T 30 S, R 19 W/E
330 feet from S section line
990 feet from E section line

R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Clinton Dean Well # 1

Operator: J. Mark Richardson
Name & Address 640 Century Plaza Bldg.
Wichita, KS 67202

County Kiowa 168.35
Well Total Depth 5180 feet
Conductor Pipe: Size 8 5/8 feet
Surface Casing: Size 8 5/8 feet 682

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor J. Mark Richardson License Number 5414
Address 640 Century Plaza Bldg., Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 28 Month: 1 Year: 19 88

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-862-5979

were: 4 1/2" at 5181' PRTD 5134' Perfs at 4743-46'

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:30 a.m. Day: 28 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 300 psi.

FEB 03 1988 2-3-88

Remarks: Used 60/40 Pozmix 6% gel by B.I. Titan. Recovered 9200' casing. (If additional description is necessary, use BACK of Form.)

INVOICED

(If desired, observe this plugging.)

Signed Richard W. Lacey (TECHNICIAN)

DATE 2-4-88

INV. NO. 19727