

1 060580

API NUMBER 15-097-21,143-0000 *R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW/4 NW/4, SEC. 5, T 30 S, R 19 W/E  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Parkin "B" Well # 1

Operator: Vincent Oil Corporation

County Kiowa *168.68*

Name & Address 125 N. Market, Suite #1110

Well Total Depth 5190' Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 513

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstates Oilfield Services Inc. License Number 5149

Address P.O. Box 329, Pratt KS 67124

Company to plug at: Hour: 9:00am Day: 4 Month: June Year: 1985

Plugging proposal received from Walter Hogan

(company name) Wheatstates Oilfield Services Inc. (phone) 316-672-7514

Work: Keep Hole full of good heavy drilling mud and spot all plugs through open ended

drill pipe. 1st plug at 1220 with 50 sacks of cement. 2nd plug at 610' with 40 sacks

of cement. 3rd plug at 510' with 50 sacks of cement. 4th plug at 40' with a solid bridge

built of one sack of hulls and a 8 5/8" wiper plug then fill the hole to surface with

10 sacks of cement. Use 60/40 pozmix 2% gel 3% cc for cement. Anhydrite was at 1200' to 1250

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:30 am Day: 4 Month: June Year: 19 85

ACTUAL PLUGGING REPORT Kept Hole full of good heavy drilling mud and spotted all plugs

through open ended drill pipe. 1st plug at 1220' with 50 sacks of cement. 2nd plug at

610' with 40 sacks of cement. 3rd plug at 510' with 50 sacks of cement. 4th plug at

40' with a solid bridge built of one sack of hulls and a 8 5/8" wiper plug then filled

the hole to the surface with 10 sacks of cement. circulated the rat \_\_\_\_\_

cement. Circulated the mouse hole with 10 sacks of cement. *RECEIVED*  
*STATE CORPORATION COMMISSION*

Remarks: Sun oil well cementing pumped the 60/40 pozmix 2% gel 3% cc cement.

(If additional description is necessary, use BACK of this form.) *CONSERVATION DIVISION*  
*Wichita, Kansas*

**INVOLVED**  
(did/did not) observe this plugging.

DATE 6-20-85

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 8651