

1 040335

10-11

To: 2  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,052-000/

C SE SW, SEC. 12, T 30 S, R 19 W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Kane Well # 1-12

Operator: Graham-Michaelis Corporation

County Kiowa 166.04

Name & Address P.O. Box 247

Well Total Depth 5109 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 844

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 11 Month: 10 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5102' PBTD 5100' Perfs at 5056-62'

1st plug sand back to 5000' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 sx hulls and

120 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 a.m. Day: 11 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 700 psi and shut in 400 psi.

10-19-89 001191989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3600' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

(copy / retained) observe this plugging.

DATE 10-24-89

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 26195

10-11 DEC 15 1989