

1060216

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-23,457.0000  
SW NW SE SEC. 7, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME STECKLEIN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS

144.07

OPERATOR LICENSE # 31627

WELL TOTAL DEPTH 4433 FEET

OPERATOR: WHITETAIL CRUDE, INC.

PRODUCTION CSG: SIZE 5 1/2" @ 4423' WITH 165 SX

NAME AND PO BOX 544

SURFACE CASING: SIZE 8 5/8" @ 779.5' WITH 275 SX

ADDRESS NESS CITY, KS 67560-0544

RECEIVED

ABANDONED OIL WELL  GAS WELL  INPUT WELL  STATE CORPORATION COMMISSION D/A

OTHER WELL AS HEREINAFTER INDICATED

AUG 4 2000

PLUGGING CONTRACTOR SWIFT SERVICES

LICENSE NUMBER 32382

ADDRESS PO BOX 466 NESS CITY, KS 67560

CONSERVATION DIVISION  
Wichita, Kansas

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 01 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES (PHONE) 785-798-2300

WERE: PERFS AT 4423-33

SANDED TO 4330' THEN 4 SX CEMENT. 1ST PLUG AT 1600' WITH 50 SX CEMENT. 2ND PLUG AT 830' WITH 50 SX CEMENT. 3RD PLUG AT 350' WITH 40 SX CEMENT. 4TH PLUG PULLED REST OF CASING AND TOPPED OFF WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 01 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 4330' THEN 4 SX CEMENT. 1ST PLUG AT 1600' WITH 50 SX CEMENT. 2ND PLUG AT 830' WITH 50 SX CEMENT. 3RD PLUG AT 350' WITH 40 SX CEMENT. 4TH PLUG PULLED REST OF CASING AND TOPPED OFF WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY SWIFTS. RECOVERED 1760' OF 5 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED

Michael J. Maier  
(TECHNICIAN)

FORM CP-2/3

DATE 8/10/00

INV. NO. 1060339