

To: 1 071028 2-20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,887.0000 1470
NE SW, SEC. 7, T. 20 S, R. 23 W/E
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131
Operator: Thunderbird Drilling, Inc.
Name & Address P.O. Box 97
Ellinwood, KS 67526

Lease Name Petersilie Well # A-4
County Ness 144.07
Well Total Depth 4433 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 575

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:45 a.m. Day: 20 Month: 2 Year: 1992

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

was: 5 1/2" at 4426' w/100 sx cement, Perfs at 4291-4338'
1st plug sand bridges at 989', dump 5 sx cement on top;
2nd plug pump 225 sx cement down 8 5/8".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:15 a.m. Day: 20 Month: 2 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sand bridged at 989', pumped 5 sx cement,
2nd plug pumped 200 lbs. hulls ahead of 200 lbs. hulls in first part of 225 sx cement.
Maximum pressure 400 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
2-26-92
FEB 26 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 720' of 5 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED
do not observe this plugging.

DATE 3-9-92
INV. NO. 34692

Signed Dan Andra
(TECHNICIAN)