

1 070273

DEC 23 1986

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,367.0000

C. SW SE, SEC. 7, T. 20 S, R. 23 W/E
660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Stecklein Well # 1

Operator: Graham-Michaelis Corporation

County Ness

Name:

Address P.O. Box 247,

Well Total Depth 4419 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 602

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Graham-Michaelis Corporation License Number 5134

Address P.O. Box 247, Wichita, KS 67201

Company to plug at: Hour: 4 p.m. Day: 23 Month: 12 Year: 1986

Plugging proposal received from Dave Patterson

(company name) Graham-Michaelis (phone) 405-256-6491

were: 4 1/2" at 4410' Open hole 4410-19 1/2' Perfs 4298-4303' Squeeze at 966' Elevation 2307' GL

1st plug pump down 4 1/2" with 2 sx hulls and enough Econolite to fill to 4410',

hook onto 8 5/8" and try pumping cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 5 p.m. Day: 23 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 800 lbs. hulls, and 100 sx ATL cement.

Maximum pressure 1200 psi and shut in 500 psi.

Remarks: Used ATL cement by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-5-87

Signed Dan Jordan

(TECHNICIAN)

INV. NO. 15754 FEB 10 1987

12-23

FORM CP-2/3
Rev. 01-84