

11-1

13/R

4 - 062538

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,495-0000
SE NE NW /4 SEC. 33, 20 S, 13 W
990 feet from S section line
2310 feet from E section line

Operator license# 5097 Lease Hiss well # 1

Operator: Martin Oil Producers, Inc. County Barton

Address: 150 N. Main #1010 Wichita, Kansas 67202
Joe Moreland - 316-264-0352
Well total depth 3566 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 275 feet w/200 sks.

115.89

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Allen Drilling License#

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 9:15A.M Day: 1 Month: November Year: 91

Plugging proposal received from: Mike Kern

Company: Allen Drilling Phone: 316-264-0352

Were: Order 135 sks. 60/40 posmix - 6% gel. - 3% cal. cl. - 1 sk. flocele and 8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 9:15A.M, Day: 1, Month: November, Year: 91

Actual plugging report:
1st. plug at Arbuckle 3526' w/25 sks.
2nd. plug at 775' w/ 25 sks.
3rd. plug at 325' w/60 sks. - 1 sk. flocele.
4th. plug at 40' w/10 sks.
15 sks. in Rathole.
Water well 10 sks.

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1991

Remarks: Cemented by: Halliburton

CONSERVATION DIVISION
Wichita, Kansas

I did [] / did not [X] observe the plugging. Gilbert G. Scheck e.a.g.

INVOICED

DATE 12-4-91
INV. NO. 33929

(agent)
Form CP-2/3