

4-23

4-010251

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-15940.0000

C SE SW NW /4 SEC. 32 , 20 S, 13 W
2970 feet from S section line
4290 feet from E section line

Operator license# 5310

Lease: Hartman Well # 2

Operator: Four-Way Operating

County: Barton 115.77

Address: P.O. Box 698
Great Bend, Kansas 67530

Well total depth 3562 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 335 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# _____

Address: Russell, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 23 Month: April Year: 1997

Plugging proposal received from: Jim Rockhold

Company: Four-Way Operating Phone: 316-786-0150

Were: Shoot off pipe. Pull to 1500' and pump 105 sxs with 300# hulls. Pull to 825' and pump 35 sxs with 200# hulls. Pull to 375' and pump 40 sxs. Pull to 150' and pump 20 sxs.

RECEIVED
KANSAS CORP COMM
1997 MAY -1
A
S

5-1-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00 P.M. , Day: 23 , Month: April , Year: 1997

Actual plugging report: Sanded to 3050' with 5 sxs. Shot off at 2700'. Pulled to 1500' and pumped 105 sxs with 300# hulls - 60/40 - 10% gel. Pulled to 815' and pumped 35 sxs with 200# hulls. Pulled to 375' and pumped 40 sxs. (circulated) Cement fell to about 50'. Cement falling while topping off. Pumped 70 sxs to top off. Cement at 15' on April 24, 1997.

Remarks: _____
Condition of casing(in hole): GOOD BAD _____ Anhy plug: YES NO _____
Bottom plug(in place): YES , CALC _____ , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____ , CASING . Elevation: 1902 GL

INVOICED
MAY 02 1997

[] observe the plugging.

Con Moran
(agent)

DATE _____
INV. NO. 48049