

4-050311

7-20

RECEIVED
STATE CORPORATION COMMISSION

7-27-98

JUL 27 1998

API Number: 15-009-159450000

CONSERVATION DIVISION

Wichita, Kansas

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW NW SE /4 SEC. 32, 20 S, 13 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5310

Lease: Hiss Well # 1

Operator: Four Way Operating, Inc.

County: Barton 115.48

Address: P.O. Box 698
Great Bend, Kansas 67530
316-792-2506

Well total depth 3553 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 146 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: License#

Address:

Company to plug at: Hour: A.M. Day: 20 Month: July Year: 1998

Plugging proposal received from: James Rockhold

Company: Phone:

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
10 3/4" at 146' w/125 sxs. 7" at 3544' w/100 sxs.
Perfs from 3414' - 3479'. Dakota 0' - 200'. Anhydrite 778' - 798'.
Salt 1265' - 1605'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 4:30 P.M. Day: 20, Month: July, Year: 1998

Actual plugging report: Ran tubing to 1618' - pumped 75 sxs cement & 200# hulls.
Pulled tubing to 780' - pumped 40 sxs cement and 150# hulls. Pulled tubing to 408' - pumped
40 sxs cement and 150# hulls. Pulled tubing to 150' - pumped 195 sxs cement.
Cement circulated to surface.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 1891 GL

I did [X] / did not [] observe the plugging.

Martin Miller
(agent)

INVOICED

DATE 7-30-98
INV. NO. 51065