

4-060627

12-9

15.009.02045.0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 11-05-61

SE NW NE /4 SEC. 34 , 20 S, 13 W
4290 feet from S section line
1650 feet from E section line

Operator license# 4540 Lease McDonald well # 3

Operator: Riverside Petroleum Company County Barton

Address: 314 E. Santa Fe Well total depth 3575 feet ^{116.19}
Ellinwood, Kansas 67526 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 263 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 1:00P.M. Day: 9 Month: December Year: 94

Plugging proposal received from: Kevin Strube

Company: D.S. & W. Sell Servicing, Inc. Phone: 316-587-3361

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.
Pull while pulling casing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:45P.M., Day: 9, Month: December, Year: 94

Actual plugging report: 8 5/8" to 263'. 5 1/2" to 3573'. Sand to 3225'
and spotted 5 sxs. cement with dump bailer. Cut casing loose at 2719'
and pulled to 1575'. Mixed and pumped 110 sxs. cement with 300# hulls.
Pulled casing to 800' and pumped 30 sxs. cement with 100# hulls. Pulled
casing to 300' and circulated cement to surface with 80 sxs. cement.
Pulled casing and topped with 5 sxs. cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1879

I did / did not X observe the plugging.

[Signature] DEC 27 1994

INVOICED
DATE 1-5-95
INV. NO. 41974

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
Form CP-2/3