

4-041561

1-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1960

SW NE NE /4 SEC. 34 , 20 S, 13 W  
4290 feet from S section line  
990 feet from E section line

Operator license# 4054 Lease McDonald well # 1

Operator: Riverside Petroleum Company County Barton

Address: 314 E. Santa Fe Well total depth 3557 feet  
Ellinwood, Kansas 67526 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 243 feet  
w/250 sxs.

115.60

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas - Great Bend, Kansas

Company to plug at: Hour: 9:00A.M. Day: 25 Month: January Year: 94

Plugging proposal received from: Lloyd Bryant

Company: Riverside Petroleum Company Phone: \_\_\_\_\_

Were: Perf. salt @ 1550' - Anhy. @ 730'. 7-28-1980 squeeze casing  
at 388' - 462' with 150 sxs. pozmix plus 100 sxs. common cement circulate  
at surface. Ordered 175 sxs. 60/40 pozmix - 10% gel with 1/4# F.C.  
plus 500# hulls plus 10 sxs. gel. 5 1/2" casing set @ 3523' w/150 sxs.  
cement.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 1:15P.M., Day: 25, Month: January, Year: 94

Actual plugging report: R.I.H. with tubing to 3340'. Spot 50 sxs.  
cement with 300# hulls followed with 10 sxs. gel. Pull tubing to 1550'.  
Spot 40 sxs. cement. Pull tubing to 725'. Spot 60 sxs. cement to  
circulate at surface. Pull tubing - squeeze casing with 15 sxs. cement.  
Max. 300#. S.I.P. 100#. Hooked-up to 8 5/8" S.P. Pressured to 500#.

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 4 1994

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  NO   
Plugged through TUBING  , CASING  . Elevation: \_\_\_\_\_ GL

I did  observe the plugging. Dennis L. Hamel

(agent)  
Form CP-2/3

INVOICED  
DATE FEB 07 1994  
INV. NO. 39889  
1-25