

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-033-21627-01-00
 Spot: NENWNWNW Sec/Twnshp/Rge: 34-33S-17W
5365 feet from S Section Line, 4825 feet from E Section Line
 Lease Name: CARLISLE 3317 Well #: 1-27H
 County: COMANCHE Total Vertical Depth: 4787 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5137		WITH 50 SX CMT
COND	13.375	242		WITH 400 SX CMT
L1	4.5	9964		TOP OF LINER @ 5187'
PROD	7	5606	1742	WTH 325 SX CMT
SURF	9.625	1008		WITH 435 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/02/2018 9:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5137' & 50 SX CMT. PLUG AT 1050' WITH GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 04/02/2018 10:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5137'. CIRCULATED THE HOLE WITH 190 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 1050' WITH 100 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8632	8907		
8210	8538		
7772	8110		
7298	7646		
6808	7186		
6286	6740		
5778	6186		
5338	5688		

INVOICED
 APR 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD=9966'

4-18-18

Plugged through: TBG

District: 01

RECEIVED
 APR - 6 2018
 KCC DODGE CITY

Signed _____ (TECHNICIAN)

SA