

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20194-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 9-9S-19W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MC CLELLAN Well #: 3
County: ROOKS Total Vertical Depth: 3558 feet

Operator License No.: 35125
Op Name: STROKE OF LUCK ENERGY & EXPLOR
Address: PO BOX 98
TECUMSEH, KS 66542

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3554		150 SX
SURF	8.625	203		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2018 11:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BUTCH DRYLIE Company: STROKE OF LUCK ENERGY & EXP Phone: (785) 650-4404

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
CIBP at 3558'
Production perforations: 3340' - 3473'

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2018 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

ELI perforated 5 1/2" casing at 1500' and 825'. Ran tubing to 3311' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2367' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 1617' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 848' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus. Visually checked cement and cement was to surface.

GPS: 39.28122N -099.45518W

Perfs:

Top	Bot	Thru	Comments
3471	3473		
3452	3454		
3436	3438		
3417	3419		
3340	3342		

Remarks: GLOBAL CEMENTING TICKET # 3221

Plugged through: TBG

INVOICED

APR 18 2018

4-18-18

District: 04

Signed _____

Pat Bedore

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

JAN 23 2018

FEB 23 2018

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS