

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21624-01-00
Spot: SWSESESE Sec/Twnshp/Rge: 7-22S-7W
280 feet from S Section Line, 435 feet from E Section Line
Lease Name: SIEGRIST 2207 Well #: 7-1H
County: RENO Total Vertical Depth: 3585 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		42 SX CEMENT
I1	7	3880		390 sx cement
L1	4.5	8004		350 sx cement
PROD	4.5	8004		350 SX
SURF	9.625	369		270 SX
T1	2.875	2875		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2017 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Revd. from: RANDY SUMMERS Company: _____ Phone: (620) 896-7200

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/15/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TOOH WITH 89 JOINTS 2 7/8" TUBING AND ESP. SET CIBP @ 3230'. DUMP BAIL 7 SXS CEMENT ON CIBP. TIH TO 1100' AND SPOT 50 SXS CEMENT. PULL UP TO 600' AND CIRCUALTE CEMENT TO SURFACE WITH 110 SX CEMENT. TOOH. DIG OUT WELLHEAD. CUT OFF. FILL SURFACE WITH 7 SXS CEMENT. WELD ON ID PLATE.

Perfs:

Top	Bot	Thru	Comments
7630	7854		
7334	7558		
7035	7262		
6742	6966		
6442	6670		
6180	6374		
5858	6078		
5558	5782		
5262	5486		
4966	5190		
4616	4890		

INVOICED
APR 18 2018
4-18-18

Remarks: BASIC ENERGY WAS CEMENTERS ON THIS JOB. TICKET #16135. DENIED TA - NO LEASE TMD = 8015

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)

✓