

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21629-01-00
Spot: SENWNEW Sec/Twnshp/Rge: 4-23S-8W
370 feet from N Section Line, 1785 feet from W Section Line
Lease Name: REFFNER 2308 Well #: 4-1HN
County: RENO Total Vertical Depth: 3692 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		30 SX CEMENT
I1	7	3941		320 sx cement
L1	4.5	5087		367 sx cement
PROD	4.5	5087		367 SX
SURF	9.625	327		270 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2017 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDY SUMMERS Company: _____ Phone: (620) 896-7200

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/21/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 3230' AND CAP WITH CEMENT. RAN BOND LOG - TOC AT 3000'. TIH WITH TUBING. CIRCULATE HOLE WITH GELLED WATER. TOOH. PERFORATE 7" AT 1260'. RD WLJ. PUMPED 80 SXS CEMENT AND DISPLACED TO 1000'. LET CEMENT SET 2 HOURS. TRIED TO PRESSURE TEST TO 500#. GOT TO 380# AND BROKE BACK. NEXT DAY PRESSURE TEST CASING TO 500#. TAG TOC @ 973'. PERFORATE 7" @ 725'. ESTABLISH CIRCULATION. CIRCULATE CEMENT TO SURFACE WITH 325 SXS CEMENT. CUT OFF WELLHEAD. WELD ON ID PLATE.

Perfs:


Remarks: BASIC ENERGY CEMENTERS - TICKET #16136A - NO LEASE - DENIED TA TMD = 8722

Plugged through: TBG

INVOICED
APR 18 2018
4-18-18

District: 02

Signed _____



(TECHNICIAN)

