

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21631-01-00
Spot: SENWNENW Sec/Twnshp/Rge: 4-23S-8W
380 feet from N Section Line, 1785 feet from W Section Line
Lease Name: REFFNER 2308 Well #: 4-2HS
County: RENO Total Vertical Depth: 3699 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		30 sx cement
I1	7	4082		350 sx cement
L1	4.5	8064		340 sx cement
PROD	4.5	8064		340 SX
SURF	9.625	342		270 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2017 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDY SUMMERS Company: _____ Phone: (620) 896-7200

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/21/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN BOND LOG FROM 1700' TO SURFACE. TOC AT 1010'. DUMP BAIL 7 SXS CEMENT ON CIBP AT 3380'. TIH WITH TUBING AND CIRCULATE GELLED WATER. TOOH TO 1250' AND PUMP 50 SXS CEMENT PLUG. TOOH. WIRELINE PERFORATED 7" CASING AT 710'. ESTABLISH CIRCULATION AND CIRCULATE CEMENT TO SURFACE WITH 330 SXS CEMENT. CUT OFF WELLHEAD. WELD ON ID PLATE.

Perfs:

Remarks: BASIC ENERGY CEMENTERS - TICKET #16136A - NO LEASE - DENIED TA TMD = 8071

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
APR 18 2018
4-18-18