

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-031-22528-00-00  
Spot: N2NESESE Sec/Twnshp/Rge: 8-21S-14E  
1292 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BOWMAN (PIERATT) Well #: 2-HP  
County: COFFEY Total Vertical Depth: 2098 feet

Operator License No.: 32044  
Op Name: TRIMBLE & MACLASKEY OIL LLC  
Address: 110 SOUTH ST PO BOX 171  
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1451		
PROD	4.5	1451		200 SX
SURF	8.625	40		35 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2018 9:00 AM  
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC  
Proposal Rcvd. from: JIM THWEATT Company: \_\_\_\_\_ Phone: (620) 836-2000

Proposed Plugging Method: Well has 200 sacks cement from 2098 to 1451 50 ft cement plug at 1340 ft 50 ft cement plug at 500 ft Cement from 250 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/08/2018 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1340', pumped 15 sxs cement, pulled tubing to 500', pumped 10 sxs cement, pulled tubing to 250' pumped 30 sxs cement to surface. gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1343	1347		

RECEIVED  
KCC DIST # 3  
FEB 12 2018  
CHANUTE, KS  
MH

Remarks:

Plugged through: TBG

4-18-18 APR 18 2018

INVOICED

District: 03

Signed Mike Heffern  
(TECHNICIAN)

