

15.135.20225.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 135 - 20,225 (of this well) ✓
Lease Owner Pickrell Drilling Company
Address 205 Litwin Bldg., 110 N. Market Wichita, Kansas, 67202
Lease (Farm Name) Nelson "B" Well No. 2
Well Location C NW NE Sec. 36 Twp. 20 S Rge. (E) (W) 21 W
County Ness Total Depth 4405' Field Name Steffen
Oil Well X Gas Well Input Well SWD Well Rotary D & A
Well Log attached with this application as required yes
Date and hour plugging is desired to begin June 15, 1981

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Danny Biggs Address 3807 22nd St. Great Bend, Ks. 67530

Plugging Contractor Kelso Casing Pulling License No. 683
Address Box 176 Chase, Kansas, 67524

Invoice covering assessment for plugging this well should be sent to:
Name Pickrell Drilling Company
Address 205 Litwin Bldg., 110 N. Market Wichita, Kansas, 67202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas, 67202
JUN 12 1981
672-81

169

Signed: [Signature]
Applicant or Acting Agent

Date: 6-11-81

Approved
WLB 2-20-69

15.135.20225.0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 1-7-69
Rotary Drilling Completed 1-15-69

LOCATION: Nelson "B" No. 2
C NW NE Sec. 36-20S-21W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Ran 261.38' (14 jts.) used 28# 8 5/8" surface casing set at 261' KB and cemented with 160 sacks cement. Completed 3:45 PM, Jan. 7, 1969. Circulated.
Ran 4415.93' (140 jts.) 5 1/2" OD 14# casing set at 4401' KB (4' off bottom) and cemented with 135 sacks 50-50 Pozmix, 4% gel followed by 35 sacks common cement. Circulated. Completed 11:15 PM, Jan. 15, 1969

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Post Rock	C. F. S.
261	Shale & Shells	4343'
600	Shale	4390'
845	Red Bed & Shale	4405'
1055	Sand	
1200	Shale & Sand Streaks	
1416	Shale	
1453	Anhydrite	Slope Tests
2364	Shale	2500'
2500	Shale & Lime	3000'
2630	Lime	3500'
2750	Lime & Shale	4000'
3150	Shale & Lime	
3410	Shale	
3700	Shale & Lime	
4245	Lime & Shale	S. L. M.
4305	Lime	4026'
4400	Lime & Shale	
4405	Mississippi, RTD	

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1981
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

day of February, 1969, before me the undersigned, a Notary Public, in and for the aforesaid, personally appeared C. W. Sebitts, to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and he acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free act and deed of such company, for the uses and purposes therein set forth.

My commission expires: May 10, 1970

[Signature]
Notary Public
L. M. Whiting

