

State of Kansas



15-135-20126-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Kolhrus of Birmingham- Bartlett Drlg. has this date requested permission to plug the following described well:

Mr. Kolhrus guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Miner "F" Well No. 2

Location: 150° NE of C SE SE Sec. 36 Twp. 20 Rge. 21 (E)(W) X

County Ness Total Depth 4399 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kolhrus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600° and displace 70 sc cement thru drill pipe. Heavy mud to 240° set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40° set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo J. Massey
Conservation Division Agent