

State of Kansas



15.135.20814-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust

Complete Address: Box 187, Logan, Ks.

Lease Name: Minor Well No. 1

Location: SW NE Sec. 7 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4460' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent