



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 14 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Calvin Roberts of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Don Searle guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 352 No. Broadway, Wichita, Kansas

Lease Name: Hiss "G" Well No. # 2

Location: NE NE SW Sec. 33 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3604 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Calvin Roberts was instructed to plug the well as follows:

8 5/8" 325' Cwc.
Fill hole with heavy mud to 300', set plug with 1/4 sax
hulls, & displace 25 sax cement thru drill pipe. Mud to
35', 1/2 sax hulls, plug, & displace 10 sax cement,
cement to base of cellar.

Very truly yours,

Don Searle
 Conservation Division Agent