



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman & Iannitti Drlg. has this
date requested permission to plug the following described well:

Mr. L. E. Phillips guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Company

Complete Address: Suite 1532, 125 North Market, Wichita, Kansas
67202

Lease Name: Hiss Well No. # 1

Location: SW NE NW Sec. 33 Twp. 20 Rge. 13 (E)(W) W

County: Barton Total Depth 3165 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jack Flake was instructed to plug the well as follows:

8 5/8" 372' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 40 sax
cement thru drill pipe. Mud to 350' & displaced 25 sax cement thru
drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax
cement with Halliburton Cementing Company's pump truck, cementing to
base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent