

State of Kansas



15.009.30203.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

SEP 5 1967

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Thomas M. McCaul, of Circle Oil Company, Inc. has this date requested permission to plug the following described well:

Mr. Thomas M. McCaul guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Hiss Well No. # 1

Location: NE NE NW Sec. 33 Twp. 20 Rge. 13 (E)(W) W

County Barton Total Depth 3637 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. D. B. Pulley was instructed to plug the well as follows:

TD-3637' 8 5/8" 217' 5 1/2" 3634'

Sanded hole back to 3584' & dumped 4 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud & 85 sax cement with pump

truck, cementing from 260' to base of cellar.

Very truly yours,

Don Adrian  
Conservation Division Agent