



15.009.19457.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Monte Chadd of Petroleum, Inc. has this

date requested permission to plug the following described well:

Mr. Petroleum, Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas

Lease Name: Hiss "B" Well No. # 1

Location: SE SE SE Sec. 32 Twp. 20 Rge. 13 (E) (W) W

County Barton Total Depth 3617 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" 317' Cwc.

Sanded hole back to 3400' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mud to 300'; set 10' rock bridge; displaced 4 sax

cement with dump bailer. Let set over night; bailed hole dry;

displaced 3 1/2 yds. Ready-mix cement, cementing to base of cellar.

Very truly yours,

John Unruh
Conservation Division Agent