

State of Kansas



15.009-19469.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Chew of Jim Chew has this

date requested permission to plug the following described well:

Mr. Jim Chew guarantees payment of the plugging fee.

Operator's full Name: Jim Chew

Complete Address: Box 526, Lyons, Kansas

Lease Name: Weathers Well No. # 1

Location: C S/2 NW NE Sec. 35 Twp. 20 Rge. 14 (E)(W) W

County Barton Total Depth 3527 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ted Nutt was instructed to plug the well as follows:

8 5/8" 813! Cwc.

Set bottom plug @ 3280' & dumped 5 sax cement with dump

bailer. Pulled pipe. Set bottom plug @ 350'; displaced

5 sax cement with dump bailer. Let set over night.

Bailed hole dry; displaced 5 yds. Ready-mix cement,
cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent