



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marty Hayes of Alpine Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Jon T. Williams, Jr. guarantees payment of the plugging fee.

Operator's full Name: Alpine Drilling Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Weathers "B" Well No. # 1

Location: S/2 SW SE Sec. 35 Twp. 20 Rge. 14 (E)(W) W

County: Barton Total Depth 3650 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Marty Hayes was instructed to plug the well as follows:

8 5/8" 337' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 320' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement

with Globe Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Brown  
Conservation Division Agent