

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 30 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Russell Overly of Bea Drilling Co., Inc. has this

date requested permission to plug the following described well:

Mr. Overly guarantees payment of the plugging fee.

Operator's full Name: Muir-Thompson, Inc.

Complete Address: 201 Garlinghouse Bldg., 820 Quincy, Topeka, Ks.

Lease Name: Vincent Well No. 1

Location: NE NW SW Sec. 34 Twp. 20 Rge. 9 (E) (W)

County Rice Total Depth 3455' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Overly was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push
plug and $\frac{1}{4}$ sack hulls to 200' and cement with 20 sacks
thru drill pipe. Fill hole with mud to 35'. Push plug
and $\frac{1}{4}$ sack hulls to 35' and cap hole with 10 sacks cement.
Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

Conservation Division Agent