



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED
MAY 2 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 29, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Jay-Bee Oil Company, Inc.

Complete Address: 515 Union Center, Wichita, Kansas 67202

Lease Name: Hartle Well No. 1

Location: NW SE NW Sec. 34 Twp. 20 Rge. 9 (E)(W) X

County: Rice Total Depth 3430' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Stella J. Somers
Conservation Division Agent