



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

January 31, 1973

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leonard Williamson of Duke Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Williamson guarantees payment of the plugging fee.

Operator's full Name: Icer Addis

Complete Address: 312 Petroleum Bldg., Wichita, Kansas 67202

Lease Name: John Caywood Well No. 3

Location: NE NW SE Sec. 30 Twp. 20 Rge. 9 (W) (X)

County: Rice Total Depth 3290' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Williamson was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 25 sacks cement through

drill pipe at 500'. Pump 25 sacks cement through drill pipe at 210'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent