

State of Kansas



15.009.04980.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. C. E. Byars of Charles Hulme Drilling, Con has this  
date requested permission to plug the following described well:

Mr. Charles Hulme guarantees payment of the plugging fee.

Operator's full Name: Charles Hulme Drilling Contractor

Complete Address: Box 836, Great Bend, Kansas

Lease Name: Tammen Well No. # 4

Location: NE NE NE Sec. 31 Twp. 20 Rge. 12 (E)(W) W

County Barton Total Depth 3490 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. C. E. Byars was instructed to plug the well as follows:

8 5/8" 271' Cwc.

Sanded hole back to 3460' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 265', set 15' rock bridge, & displaced

10 sax cement. Let set over night, bailed hole dry, & displaced

4 yds. ready-mix cement, cementing from 250' to base of cellar.

Very truly yours,

Don Tripp  
Conservation Division Agent