



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 7 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. J. O. Forbes of Forbes Casing Pulling Inc this.

10-7-1963

date requested permission to plug the following described well:

Mr. J. O. Forbes guarantees payment of the plugging fee.

Operator's full Name: Forbes Casing Pulling Inc.

Complete Address: Box 221, Great Bend, Kansas

Lease Name: Sandrock Well No. # 1

Location: SW SW SE Sec. 21 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3601 oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. D. B. Pulley was instructed to plug the well as follows:

8 5/8" 252' Cwc.

Sanded hole back to 3530' & dumped 5 sx cement wh/dump  
bailer. Pulled pipe. Set plug @ 250'; set rock bridge &  
dumped 25 sx cement wh/dump bailer on bridge. Mud to 40';  
set rock bridge; displaced 10 sx cement, cementing to  
base of cellar.

Very truly yours,

Don Truman  
 Conservation Division Agent