

State of Kansas



15.009.05246.0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1963

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Cecil M. Olson of Duke Drilling Company has this

date requested permission to plug the following described well:

Mr. Lynn Duke guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas

Lease Name: Luse Well No. # 1

Location: SW SE SW Sec. 21 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3575 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Cecil M. Olson was instructed to plug the well as follows:

8 5/8" 275' Cwc.

Filled hole with heavy mud to 270', set plug with 1/4
sax hulls, & displaced 25 sax cement thru drill pipe.

Mud to 35', 1/2 sax hulls, plug, & displaced 10 sax
cement, cementing to base of cellar.

Very truly yours,


Conservation Division Agent