

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 76-33

LOCATION NE-SE-SE

SEC. 34 TWP. 20 RGE. 14 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1. Lease Pritchard

Operator Rocket Drilling Co. Address 352 N. Broadway, Wichita, Mo.

Field County Barton

Total Depth 3565 Feet.

Plugging Contractor West Supply Co, Inc.

Plugging Contractor's License No. 14

Address Chase, Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 800' C.W.C. 5 1/2" O.D. @ 3564 1/2
up 100' st cem. Plugged back to 3493'. Top Perf. 3411'
sanded hole to 3400', dumped 5' st cem. Shot off
and pulled 5 1/2" casing. Mudded hole to 300'
set rock bridge and run 20' st cem. mud
to 35' rock bridge and run 10' st cem to
base of cellar

PLUGGING
FILE SEC 34 T 20 R 14 W
BOOK PAGE 76 LINE 33

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 - 1954

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date Dec 4, 1954