

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-20855-00-00

LEASE NAME Welsh

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from (S) Section Line

2970 Ft. from (E) Section Line

SEC. 19 TWP. 20 RGE. 12W (E) or (W)

LEASE OPERATOR DJ OIL OPERATIONS

COUNTY Barton

ADDRESS 305 E. 6th Street. Ellinwood, Kansas 67526

Date Well Completed _____

PHONE# (620) 564-2759 OPERATORS LICENSE NO. 31199

Plugging Commenced 5-31-01

Character of Well Oil

Plugging Completed 6-1-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3547'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	250'	None
				4-1/2"	3545'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from _____ feet to _____ feet each surface. Perforated well @1500' and 685'. Ran 2-3/8" tubing to 2000'. Pumped 10 sks. cement down surface, press. to 300#. Pumped down 2-3/8" tubing, 100 sks. cement w/300# hulls and circulated to surface. Pulled tubing out, hooked onto 4-1/2" and pumped 80 sks. cement. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DJ Operations

RECEIVED
JUN 6 2001

STATE OF Kansas COUNTY OF Rice, ss.

6-6-01
CONSERVATION DIVISION

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of June, 2001

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-