

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Wichita State Office Bldg.  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-009-21,067-0000

LEASE NAME WELSH

WELL NUMBER #3

3300 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 19 TWP. 20S RGE. 12 (E) or (W)

COUNTY BARTON

Date Well Completed 09/22/76

Plugging Commenced 02/27/96

Plugging Completed 02/27/96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Coas. Div.  
 office within 30 days.

LEASE OPERATOR HARTMAN OIL CO., INC.

ADDRESS P.O. Box 54 Wichita, KS. 67201

PHONE(S) (316) 636-2090 OPERATORS LICENSE NO. 30535

Character of Well Abd. input well

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 27, 1996 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation LANSING Depth to Top 3208' Bottom 3438' T.O. 3610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

3-26-96

Formation	Content	From	To	Size	Put In	Pulled out
LANSING	Oil & Water	3208'	3438'	8 5/8"	245'	None
ARRBUCKLE	Tight	3453'	3610'	4 1/2"	3565'	None
				3" liner	3270'	None

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from 1500 feet to 0 feet each set.  
 Casing in good shape. Tubing and packer stuck below 1516'. tubing was parted at 1516'; tubing below 1516' was attached to packer which was stuck, unable to recover. Ran tubing to 1500' and dumped 50 sx. cement with cement to surface. Pulled tubing and tied onto 3" liner. Pumped 10 sx. cement and locked up at 400# STP. Cementing by Allied complete.

Name of Plugging Contractor KLIMA WELL SERVICE, INC. License No. 7023

Address P. O. Box 386 - 610 W. Front Claflin, KS. 67525-0386

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HARTMAN OIL CO., INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

WILLIS E. HARTMAN

(~~XXXXXXXXXXXXXXXXXXXX~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Willis E. Hartman

(Address) P. O. Box 54 Wichita, KS. 67201

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1996

My Commission Expires: 01-19-99

