


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section/Plat.

Barton

County. Sec. 19 Twp. 20 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner. Inger Oil Company

Lease Name ~~WIKKXKXKXKXKXKX~~ Strathman Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 7-17-61 19

Plugging completed 7-20-61 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker

Producing formation Depth to top Bottom Total Depth of Well 3450 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None
				5-1/2"	3410'	2611'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3355', ran sand to 3320' and dumped 5 sacks of cement @ 3320' with dump bailer. Pulled 5 1/2" casing. Bailed fluid from 40' to 250', set 10' rock bridge from 250' to 240' and ran 20 sacks of cement @ 240'. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas
COUNTY OF Rice
Noel J. Knight ss.

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1961

My commission expires

May 20, 1961

Notary Public.

Casing Record

8 5/8

230' Cemented
w/190 sacks

T.D.

3540'

Location: SE SE NW

Section: 19-20S-12W

Barion County, Kansas

Farm: Strothman #1

Well Owner: White & Ellis et al

Contractor: White & Ellis Drig., Inc

Started: 10/15/60

Completed: 10/25/60

Elevation: 1851 K.B.

Kelly Bushing Measurement 5' above ground level

FORMATION	DEPTH	TCPS	
Sand	0-185	Hoebner	3066
Sand, Shale & Lime	265		
Red rock	660	Toronto	3091
Shale & Lime	1223		
Shale & Shells	1440	Douglas	3100
Shale & Lime	1540		
Anhydrite	1650	Kansas City	3200
Shale & Lime stks.	1765		
Lime & Shale stks.	1935	Cherty Conglomerate	3450
Lime	2080		
Lime & Shale stks.	2225	Arbuckle	3496
Shale & Lime	2605		
Lime & Shale	3000		
Lime	3115		
Lime & Shale	3180		
Shale & Lime	3200		
Lime	3432		
Shale & Lime	3450		
Conglomerate	3496		
Lime	3540		

3496
1851
1645

3200
1851
1349

Dry Hole
Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1961

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF BUTLER)

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Strothman No. 1 well completed October 25, 1960.

Howard E. Russell
Howard E. Russell, Vice President

Subscribed and sworn to, before the undersigned, a Notary Public, in and for the County and State aforesaid, this 11th day of November, 1960.

L. B. Auer
Notary Public

My Commission Expires September 26, 1964.