


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 34 Twp. 20 Rge. 14 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner Bovaird Supply Co.

Lease Name Pritchard Well No. #3

Office Address Box 897 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 8-19-66 19__

Application for plugging approved _____ 19__

Plugging commenced 8-26-66 19__

Plugging completed 9-8-66 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3557 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3540'. Pushed plug to 3100', set bridge with 30 gal. rock and sand. Mixed and ran 5 sacks cement thru dump bailer. Mudded hole to 270', set rock bridge. Mixed and dumped 5 sacks cement and 1 sack caaseal thru dump bailer. Filled hole with 4 1/2 yards ready mix to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1966
9-19-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of September, 19 66

My commission expires 21 October 1968
Sidney D. Miller
Notary Public.

Exhibit "B"

ROCKET DRILLING COMPANY
 352 North Broadway
 Wichita 2, Kansas

#3 Pritchard
 SW SW SE 34-20-14W
 Barton County, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

AUG 22 1966

OPERATIONS DIVISION
 Topeka, Kansas

Elevation: 1915 R.B.
 Spudded: April 13, 1954
 Rotary Completed: April 23, 1954
 Contractor: Rocket Drilling Company

CASING RECORD

601' 8-5/8" O.D. 24# Seamless Casing Cemented with 300 Sacks Cement.
 3553' 5 1/2" O.D. 14# Seamless Casing Cemented with 100 Sacks Cement.

DRILLERS LOG

Sand	0 to 225	Lime & Shale	1990
Blue Shale	260	Sand	2000
Sand	340	Lime	2545
Red Shale	380	Shale	2750
Sand	415	Lime & Shale	2845
Red Shale	450	Lime	3190
Red Shale & Shells	798	Lime & Shale	3516
Anhydrite	801-825	Sand	3524
Shale	1375	Shale & Chert	3552
Salt & Shale	1770	Arduckle	3554 TD
Line	1870		

I hereby certify that to the best of my knowledge and belief, the foregoing log is true and correct.

ROCKET DRILLING COMPANY

By *B. A. Parks*

STATE OF KANSAS) SS:
 (BARTON COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for the State and County aforesaid, this 28th day of April, 1954.

My Commission Expires: March 5, 1958

Patricia McBlume
 Notary Public