


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
221 Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 34 Twp. 20 Rge. 14W (E) (W)
Location as "NE/CNWxSWx" or footage from lines CSE NE SW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Asher Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/29 19 56
Application for plugging filed 4/29 verbally 19 56
Application for plugging approved 4/29 verbally 19 56
Plugging commenced 4/29 19 56
Plugging completed 4/29 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3635 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	804 1/2	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug @ 300, 1/3 sack hulls, plug and 20sacks cement fill to 40".
Second plug, 1/3 sack hulls & 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 19 56

My commission expires 6/17/58

Charles [Signature] Notary Public.
RECORDED
STATE CORPORATION COMMISSION
MAY 31 1956 3-3-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 30 R 14W
BOOK PAGE 58 LINE 5

Bennett & Roberts Drilling Co.
Lusher #1

CSE NE SW 34-20-14W
Barton County, Ks.

R.T.D. 3635'

Commenced 4/18/56
Completed 4/29/56

Casing Record
8 5/8" Set @ 804' w/480 sx cmt

----- Figures Indicate Bottom of Formation -----

Sand	205
Shale & Sand	290
Sand	340
Red Bed & Shale & sand Strks.	680
Red Bed & Shale	800
Anhydrite	830
Shale, Shells & Red Bed	1045
Shale & Shells	1570
Shale & Lime	1950
Lime	2080
Lime & Shale	3040
Lime	3165
Lime & Shale	3200
Shale	3273
Lime	3508
Lime & Shale	3549
Lime	3635

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By: *Paul Baker*

Subscribed and sworn to before me this 2nd day of May, 1956.

Clara Hummel
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC 34-20-14W
BOOK PAGE 58 LINE 5

VED
NOTARY PUBLIC
My Commission Expires 6/17/58