


WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION Give All Information Completely Make Required Affidavit Mail or Deliver Report to Conservation Division State Corporation Commission 212 No. Market Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barton

County, Sec. 34 Twp. 20 Rge. 14 X W (W)

Location as "NE/CNW/SE/SW" or footage from lines. 990' N, 330' W S/4 Cor.

Lease Owner Cities Service Oil Company

Lease Name Asher "B" Well No. 2

Office Address Box 308, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed July 15 19 54

Application for plugging filed February 7 19 72

Application for plugging approved February 11 19 72

Plugging commenced March 9 19 72

Plugging completed March 11 19 72

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production February 18 19 72

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Box 148, Russell, Kansas

Producing formation Arbuckle Depth to top 3512' Bottom 3515' Total Depth of Well 3552 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Includes entries for 8-5/8" and 5-1/2" casing.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand - 3552-3530'
5 Sacks Cement - 3530-3490'
Mud - 3490- 370'
Rock Bridge - 370- 250'
Cement - 250- Base of Cellar

RECEIVED STATE CORPORATION COMMISSION MAR 16 1972 CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company

Address Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

W. J. Devaney (employee of owner) or (owner) of the above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.

(Signature) [Signature] Box 308, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 15th day of March, 1972

My commission expires June 3, 1973

Notary Public.

WELL RECORD

15.009.02068.0000

Company Cities Service Oil Co. Well No. 2 Farm Asher "B"
 Location 990' North and 330' West of S/4 Cor. Sec. 34 T. 20 R. 14W
 Elevation 1912 (1909 Gr.) County Barton State Kansas
 Drig. Comm. June 27, 1954 Contractor Barbour Drilling Company
 Drig. Comp. July 15, 1954 Acid None
 T. D. 3552' Initial Prod. Physical Potential: 237 oil, 4% water, 24 hrs. (8-18-54)

CASING RECORD:

8-5/8" @ 817' cem. with 560 sx cem.
 5-1/2" @ 3546' cem. with 125 sx cem.

FORMATION RECORD:

sand	0-275
sand & shale	335
sand, shale & red rock	650
red rock	810
anhydrite	830
shale & shells	1300
salt & shale	1495
shale & shells	1785
shale & lime	1930
broken line	2210
broken line & shale	2340
broken line	2460
shale	2620
shale & lime	2740
lime & shale	2850
lime	3035
broken line	3105
lime	3173
shale	3176
lime & shale	3190
lime	3240
shale	3275
lime	3279
lime & shale	3285
lime	3500
lime & shale	3540
shale	3543
lime	3546
3546 STD = 3549 SLM	
lime	3552 T. D.

Corr. Heebner	3176'
Corr. Brown Limestone	3278'
Corr. Lansing	3289'
Corr. Conglomerate	3522'
Corr. Simpson Shale	3530'
Corr. Arbuckle	3546'
Penetration	6'
Total Depth	3552'

FILLUP:

65' oil in 1 1/2 hrs. at 3550 1/2
 125' oil in 2 hrs. at 3550 1/2
 742' oil in 4 hrs. 10 mins. at 3552
 912' oil in 4 hrs. 40 mins. at 3552

STFO:	750'	1°
	1000'	0°
	1500'	1°
	2000'	1°
	2500'	2°
	3000'	1°

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 9 1972
 CONSERVATION DIVISION
 Wichita, Kansas

46 3546
 1909
 -1637
 LKC 3287
 1380