


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. BOX 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 34 Twp. 20S. Rge. 14 (X) (W)  
Location as "NE/CNW/SW" or footage from lines C S/2 NE NE  
Lease Owner Cities Service Oil Company  
Lease Name Taylor "B" Well No. 4  
Office Address 700 Sutton Pl. Bldg. Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 13 19 48  
Application for plugging filed May 10 19 74  
Application for plugging approved May 13 19 74  
Plugging commenced May 23 19 74  
Plugging completed May 29 19 74  
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation Arbuckle Depth to top 3546 Bottom 3550 Total Depth of Well 3550 Feet  
Shoal depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	813'	None
				5 1/2"	3546'	1837

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3175'. Mixed and ran 5 sacks cement thru dump bailer. Tension 18". Made shots 2514', 2240', 2018'. Made shot 1825'. Pulled total string 59 joints. Mudded hole to 375', set 25' rock bridge. Plugged with 5 yards ready-mix to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1974  
CONSERVATION DIVISION  
Wichita, Kansas

6-20-74

Name of Plugging Contractor Southwest Casing Pulling Company  
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK  
W. J. Devaney (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Glenn E. Meier  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
(Signature) 209 E. William, 700 Sutton Pl. Bldg. Wichita, KS  
(Address) 67202

SUBSCRIBED AND SWORN to before me this 18th day of June 19 74

My commission expires June 3, 1977  
Glenn E. Meier Notary Public.

# WELL RECORD

Company Cities Service Oil Well No. 4 Farm Taylor "B"  
 Location 990' S & 660' W of NE Cor. Sec. 34 T. 20 R. 14  
 Elevation 1906 (1904 Gr.) County Barton State Kansas  
 Drlg. Comm. May 16, 1948 Contractor Corbett and Harbour Drilling Co.  
 Drlg. Comp. June 13, 1948 Acid None  
 T.D. 3550' Initial Prod Physical Potential: 31 oil, 4% water, 24 hours (7-13-48)

**CASING RECORD:**

8-5/8" @ 813' with 500 sacks cement.  
 600# C.C. and 300#  
 Flow seal.  
 Squeezed hole in casing at 362' with 200  
 sacks cement.  
 5-1/2" @ 3548' with 150 sacks cement.  
 Found hole in 5 1/2" casing at 2610; cemented  
 with 100 sacks.

**FORMATION RECORD:**

Surface clay and sand	0-100
sand	175
shale and shells	265
sand, shale and shells	360
shale and shells	420
red bed and shells	520
red bed, shale and shells	720
shale, shells and chalk	802
anhydrite	825
red bed	900
red bed and shale	975
shale and shells	1410
salt, shale and shells	1600
shale and shells	1665
anhydrite	1715
shale and shells	1790
lime and shale	1800
lime	1905
lime and shale	1935
shale	1955
lime	2135
shale and lime	2230
lime and shale	2325
shale and lime	2385
lime and shale	2890
lime	3542
shale and lime	3551
3551 Rotary T.D. = 3548 S.I.M.	
lime	3550 T.D.

Corr. Top Lansing	3579'
Corr. Top Simpson	3551
Corr. Top Arbuckle	3548'
Penetration	5'
Total depth	5550'

**FILL-UP**

165' oil in 55 minutes.  
 450' oil in 2 hours 10 minutes.  
 620' oil in 3 hours 10 minutes.  
 1150' oil in 6 hours 10 minutes.  
 2430' oil in 23 hours.

**SYFO:**

500'	0°
1000'	0°
1500'	0°
2000'	0°
2500'	0°
3000'	0°
3500'	0°

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 13 1974

CONSERVATION DIVISION  
 Wichita, Kansas