

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
115 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-21,336.0000

LEASE NAME Woodburn

WELL NUMBER 4

         Ft. from S Section Line

         Ft. from E. Section Line

SEC. 34 TWP. 20S RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed         

Plugging Commenced 7-20-98

Plugging Completed 7-24-98

LEASE OPERATOR Vess Oil Corporation  
ADDRESS 8100 E. 22nd. St. North, Bldg. 300, Wichita, Ks. 67226

PHONE(S) (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Case Morris (KCG District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	824'	None
				5-1/2"	3620'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from          feet to          feet each side. Plugged off bottom with sand to 3350' and 5 sacks cement. Shot pipe @2500', 2200', 2000', and 1800'. Pulled up to 15550', pumped 100 sks. cement and 300# hulls, pulled to 850', pumped 40 sks. cement and 100# hulls, pulled up to 200' and circulated 50 sks. cement, 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1998

[Signature]  
Notary Public

My Commission Expires:         

