

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
111 S. Market, Room 2078  
Wichita, KS 67202  
KANSAS CORP COMM

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-21,327.0000

LEASE NAME Woodburn

WELL NUMBER 3

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 34 TWP. 20S RGE. 14W (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-24-98

Plugging Completed 7-27-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1998 JUL 31 12:46

7-31-98

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. N., Bldg. 300, Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

Case Morris

(KCC District Agent's Name).

Is ACC-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3567'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	820'	None
				5-1/2"	3566'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack. Plugged off bottom with sand to 3350' and 5 sacks cement. Shot pipe @2400'. 2200'. pulled up to 1550'. pumped 100 sks. cement and 300# hulls. pulled to 850'. pumped 50 sks. cement and 100# hulls. pulled to 200'. circulated 40 sks. cement to surface. 60/40 pos. 10% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1998

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
Revised 05-