

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County, Sec. 34 Twp. 20 Rge. 14 (W)

Location as "NE/CNW&SW" or footage from lines C-SE-SE-NW

Lease Owner Sunray Oil Corporation

Lease Name W. H. McGreevy Well No. 1

Office Address P. O. Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 24 19 54

Application for plugging filed August 24 19 54

Application for plugging approved August 25 19 54


Plugging commenced August 24 19 54

Plugging completed August 24 19 54

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3595 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3186		8 5/8	824	none
Toronto		3202				
Douglas		3221				
Iatan		3294				
Lansing-Kansas City	water	3304	3532			
Simpson		3504				
Arbuckle	water	3585	3595			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 3595' to 300', placed 30 sax cement and 1/2 sax hulls. Mudded hole to 40', placed 20 sax cement and 1/2 sax hulls to surface. Dry hole plugged and abandoned.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company

Address Philtower Building, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.

Robert K. Crouch (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert K. Crouch

P. O. Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 54

My commission expires December 24, 1956

Notary Public.

PLUGGING
FILE SEC-34 T. 20 R. 14W
BOOK PAGE 58 LINE 39

RECEIVED
CORPORATION COMMISSION
SEP 11 1954
CONSERVATION DIVISION
Wichita, Kansas

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
August 30, 1954

Contractor: Stickle Drilling Company
Drilling commenced: August 13, 1954
Drilling completed: August 24, 1954

W. H. McGreevy #1 NW/4 Section 34-20S-14W, Barton County, Kansas

DRILLERS LOG

Sand	0-200
Shale	200-215
Shale & Shells	215-350
Red Bed	350-815
Anhydrite	815-840
Red Bed & Shale	840-1260
Shale & Shells	1260-1650
Lime & Shale	1650-1800
Lime	1800-1970
Lime & Shale	1970-2110
Shale & Lime	2110-2687
Lime & Shale	2687-3030
Lime	3030-3222
Lime & Shale	3222-3330
Lime	3330-3534
Shale & Sand	3534-3563
Lime	3563-3595TD

I, Fred E. Stickle hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's W. H. McGreevy #1 NW/4 Section 34-20S-14W- Barton County, Kansas.

Fred E. Stickle
Fred E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My commission expires

RECEIVED
OIL CORPORATION COMMISSION
SEP 11 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34-20-B-14W
BOOK PAGE 51 LINE 29