


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Barton County. Sec. 34 Twp. 20 Rge. 14 (E) (W) x  
NW SW SE  
Lease Owner Bovaird Supply Co.  
Lease Name Pritchard Well No. #4  
Office Address Box 897, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 8-19-66 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-8-66 19\_\_\_\_  
Plugging completed 9-14-66 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3555' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 3540', pushed plug to 3100', mixed and ran 5 sacks cement thru dump bailer.  
Mudded hole to 350', set 20' rock bridge. Mixed and ran 3 sacks cement thru dump bailer.  
Filled hole with 1/2 yards ready mix to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 18 1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of September, 19 66

My commission expires 24 October 1968

Sidney D. Miller  
Notary Public.

ROCKET DRILLING COMPANY  
352 North Broadway  
Wichita 2, Kansas

#4 Pritchard  
NW SW SE 34-20-14W  
Barton County, Kansas

Elevation: 1915 R.B.  
Spudded: May 10, 1954  
Rotary Completed: May 20, 1954  
Contractor: Rocket Drilling Company

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1966

COMPARISON DIVISION  
Wichita, Kansas

CASING RECORD

805' 8-5/8" O.D. 24# Seamless Casing Cemented with 300 Sacks Cement.

3550 1/2' 5 1/2" O.D. 14# Seamless Casing Cemented with 100 Sacks Cement.

DRILLERS LOG

Sand	0 to 200	Lime	1990
Blue Shale	255	Sand	1996
Sand	320	Lime	2175
Red Shale	375	Lime & Shale	2360
Sand	450	Shale	2595
Red Shale	545	Shale & Lime	2820
Red Shale & Shells	800	Lime	3151
Anhydrite	827	Lime & Shale	3302
Shale, Shells & Salt	1220	Lime	3520
Shale & Lime	1630	Simpson	3549
Lime	1824	Arbuckle	3551 TD
Sand	1830		

I hereby certify that to the best of my knowledge and belief, the foregoing log is true and correct.


ROCKET DRILLING COMPANY

BY 

STATE OF KANSAS)  
SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public, in and for the State and County aforesaid, this 25th day of May, 1954.

My Commission Expires: March 5, 1958

  
Notary Public