

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-17

API NUMBER 15-009-24761-0000
LEASE NAME Wright
WELL NUMBER "B" - 1

RECEIVED
AUG 07 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

840 Ft. from North Line of Section
1750 Ft. from West Line of Section

LEASE OPERATOR RAMA Operating Co., Inc. SPOT LOCATION 150' N & 100' E of SW Ne Nw
ADDRESS P.O. Box 159 Section 35 Township 20s Range 14w
CITY, STATE, ZIP Stafford, Kansas 67578 County Barton
PHONE # 316-234-5191 Date Well Completed 08/02/03
Character of Well Dry and Abandoned Date Plugging Commenced 08/02/03
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 08/02/03

The plugging proposal was approved on August 1, 2003 (date)
by ROGER MOSES (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 2684

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PULL IN	PULL OUT
Surface Soil and Sands	Water sands	0	210	and		
Redbeds	Shale/Siltstone	220	329	8-5/8"	333'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Received plugging orders 08/01/03 from Roger Moses. Plugged as follows using 115 sx of 60/40 Poz, 6% Gel and 1/4# sx Surf-lake: Heavy mud in hole and between all plugs; Bottom plug at 820' using 25 sx, 2nd plug at 430' using 80 sx, top plug at 40' using 10 sx cemented to surface. Plugged Rathole with 15 sx, same blend as above, no mousehole.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 5th day of August, 2003

Pamela S. Fields
(Notary Public)



My Commission Expires:

RECEIVED

AUG 07 2003

KCC WICHITA

Sterling Drilling Company, Rig #1Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509**SAMPLE LOG****Wright "B" - 1**

LOCATION:	150' N & 100' E of SW Ne Nw	Section	35	T 20s	R 14w
API:	15-009-24761-0000	Barton County, Kansas			

OWNER: RAMA Operating Co., Inc.**COMMENCED:** 28-Jul-03**CONTRACTOR:** Sterling Drilling Company, Rig #1**COMPLETED:** 02-Aug-03

TOTAL DEPTH:	DRILLER	2684	FEET
	LOGGER	2684	FEET

Ground Elevation: 1907**KB Elevation:** 1916**LOG**

0 -	3 FEET	Top Soil
3 -	15 FEET	Clay
15 -	26 FEET	Sandy Clay
26 -	210 FEET	Sand, Gravel and Clays
210 -	814 FEET	Redbeds and Shales
814 -	835 FEET	Anhydrite (Driller's)
835 -	1735 FEET	Shales and Salt
1735 -	2684 FEET	Limestone/Shale and Dolomite

CASING RECORDS**Surface/Production Casing Data:**

Spud @ 3:00 pm on 07/28/03. Drilled 12 1/4" hole to 329'. Ran 8 joints of new, 23#, 8-5/8" surface casing. Tallied 333' set at 329' KB. Cemented with 225 sacks 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 8:45 pm on 07/28/03 by Allied. Ticket # 15908. Strapped bottom

Plugging Data:

Received plugging orders 08/01/03 from Roger Moses. Plugged as follows using 115 sx of 60/40 Poz, 6% Gel and 1/4# sx Surf Flake: Heavy mud in hole and between all plugs; Bottom plug at 820' using 25 sx, 2nd plug at 430' using 80 sx, top plug at 40' using 10 sx cemented to surface. Plugged Rathole with 15 sx, same blend as above, no mousehole. Plug down at 12:30 pm on 08/02/03. Allied Cementing ticket # 15986. Reported to KCC 08/04/03.

DEVIATION SURVEYS

0 degree(s) at	329	feet
3/4 degree(s) at	1817	feet
1 degree(s) at	2360	feet
1 degree(s) at	2684	feet