



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 5, 1964

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Dick Mead of Sterling Drilling Co. has this

date requested permission to plug the following described well:

Mr. Mead guarantees payment of the plugging fee.Operator's full Name: Sterling Drilling Co.Complete Address: Box 127, Sterling, KansasLease Name: Smith Well No. 1Location: NE NE SW Sec. 4 Twp. 20 Rge. 7 (E) (W) XCounty Rice Total Depth 3688' Oil WellGas Well Input Well SWD Well D & A X Lost HoleMr. Mead was instructed to plug the well as follows:Fill hole with mud to 200'. Push plug and  $\frac{1}{2}$  sack hulls  
to 200' and cement hole with 20 sacks through drill pipe.Fill hole with mud to 40'. Push plug and  $\frac{1}{2}$  sack hulls  
to 40' and cap hole with 10 sacks cement.Bridge rathole, and cement with 2 sacks.

Very truly yours,

  
Conservation Division Agent