



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 30, 1964

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Oliver Kemp of Lario Oil & Gas Company has this
date requested permission to plug the following described well:Mr. Kemp guarantees payment of the plugging fee.Operator's full Name: Lario Oil & Gas CompanyComplete Address: 301 So. Market, Wichita, KansasLease Name: Charles W. Monroe Well No. 1Location: C NW NE Sec. 7 Twp. 20 Rge. 7 (E) (W) County Rice Total Depth 3594' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Kemp was instructed to plug the well as follows:Fill hole with mud to 230'. Push plug and $\frac{1}{4}$ sack hulls to
230' and cement hole with 20 sacks through drill pipe.Fill hole with mud to 40'. Push plug and $\frac{1}{4}$ sack hulls to
40' and cap hole with 10 sacks cement.Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent