

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-141-20456-00-00
Spot: S2NWSWSW Sec/Twnshp/Rge: 32-8S-12W
880 feet from S Section Line, 330 feet from W Section Line
Lease Name: DIXON Well #: 1-32
County: OSBORNE Total Vertical Depth: 3209 feet

Operator License No.: 5145

String Size Depth (ft) Pulled (ft) Comments

Op Name: DREILING OIL INC

PROD 5.5 3209 155 SX

Address: 1008 CODY AVE PO BOX 550
HAYS, KS 67601

SURF 8.625 218 160 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/13/2018 9:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: AVEN WEAVERLING

Company: DREILING OIL INC

Phone: (785) 623-3221

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 11 sx gel and 200 # hulls.
02/06/2013 - Port Collar cementing by Allied Cementing witnessed.

Plugging Proposal Received By: RAY DINKEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/13/2018 1:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Pulled rods and tubing. Hooked to 5 1/2" casing and pumped 22 bbls of water to load well with an injection rate of 2 bpm at 1250 psi. Pumped 25 sx cement followed by 50 sx cement w/100 # hulls mixed in. Pumped 11 sx gel followed by 130 sx cement. Pressure increased to 1500 psi. Shut down and pressure fell to 700 psi. Kicked pump in and pressure walked up to 1500 psi. Shut down and shut in with 950 psi. Bled pressure off and casing stayed full. Braden head was full of cement.

GPS: 39.30963 -098.69353

Top	Bot	Thru	Comments
2991	2994		

Remarks: QUALITY CEMENTING TICKET # 512

Plugged through: CSG

INVOICED
MAY 01 2018

District: 04

Signed Ray A Dinkel

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

MAR 28 2018

Form CP-2/3