

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-20969-00-00  
Spot: S2N2SE Sec/Twnshp/Rge: 21-16S-10W  
1650 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: STOLTENBERG D Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3350 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 1822 24TH STREET  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3253		
PROD	5.5	3349		150 SX
SURF	8.625	390		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/03/2018 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JIM LYMAN Company: DS & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/04/2018 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CHECK BOTTOM. PERFORATE AT 1350', 1000' AND 440'. RUN TUBING TO 3300' AND PUMP 35 SX'S COMMON 3% CC. PULL TUBING OUT AND COME BACK ON 4-4-18 AND TAG CEMENT AT 3209'. RUN TUBING TO 1350' AND PUMP 35 SX'S COMMON WITH 3% CC. PULL TUBING UP TO 750' AND WAIT 1.5 HOURS. RUN TUBING BACK DOWN TO 910' AND TAGGED CEMENT. PULLED I JT UP AND PUMPED 35 SX'S COMMON WITH 3% CC, PULLED TUBING UP TO 440' AND CIRCUALTED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3315	3317	CSG	

INVOICED

Remarks: THIS WELL WAS A TA - N.O.V. WELL. GRESSEL PERFORATORS. COPELAND TICKET #C-45683. MAY 01 2018

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

✓/sk